| No. | Items of work | Per | Quantity |
|---|---|---|---|
| | (2) Constructing the servants' quarters attached to the Woddarpaly a lines— | | |
| 1 | Earthworth excavating foundation and filling in foundation and basement .. | 100 C. ft. | 1,323 |
| 2 | Burnt brick in mortar .. .. .. .. | ,, | 2,007 |
| 3 | Burnt brick in mud .. .. .. .. | ,, | 2,627 |
| 4 | Burnt stone slabs 6″ thick one line dressed .. .. .. | S. ft. | 3·5 |
| 5 | Plastering with chunam .. .. .. .. | ,, | 4,450 |
| 6 | Teakwood battened doors with fittings complete as per Margat's specifications. | ,, | 225 |
| 7 | Teakwood battened windows with round iron bars ¾″ thick and fittings complete only one shutter outside as per Margat's specifications. | ,, | 120 |
| 8 | Flooring with 1½″ thick Cuddappa slabs over 3″ concrete bed and cement pointing. | 100 S. ft. | 704 |
| 9 | Teakwood work wrought and put up with wood oiling .. .. | C. ft. | 86·50 |
| 10 | Roofing with 1st class Mangalore tiles over 2″ x 1″ teak reepers with nails and wood oiling, etc., complete. | 100 S. ft. | 1,568 |
| 11 | Ridge tiles set in mortar .. .. .. .. | R. ft. | 74 |
| 12 | Teakwood finials with painting .. .. .. | each | 2 |
| 13 | Teakwood cane board 9″ wide 1″ thick with painting .. .. | R. ft. | 150 |
| 14 | Sun shades for front windows with painting and wood work, etc., complete as per plan. | each | 2 |
| 15 | Constructing chimneys, etc., as per plan .. .. .. | ,, | 2 |
| 16 | Levelling ground and cleaning site and unforeseen charges .. .. | L. S. | |
| 17 | White and colourwashing as per plastering .. .. .. | 100 S. ft. | 4,450 |
| 18 | Chocolate painting, 2 coats .. .. .. .. | ,, | 690 |
| | (3) Constructing scavenger's shed— | | |
| 1 | Earthwork excavating foundation and filling in foundation and basement .. | 100 C. ft. | 540 |
| 2 | Burnt brick in mortar .. .. .. .. | ,, | 748 |
| 3 | Burnt brick in mud .. .. .. .. | ,, | 1,332 |
| 4 | Burnt stone slabs 6″ thick one line dressed .. .. .. | S. ft. | 121 |
| 5 | Plastering with chunam .. .. .. .. | 100 S. ft. | 2,619 |
| 6 | Teakwood battened doors with fittings complete as per Margat's specifications. | Sft. | 58 |
| 7 | Do windows with round iron bars ¾″ thick and fittings complete only one shutter outside as per Margat's specification. | ,, | 20 |
| 8 | Teakwood battened ventilators with round iron bars ¾″ thick and fittings complete only one shutter outside as per Margats' specification. | ,, | 11 |
| 9 | Teakwood work wrought and put up with wood oiling .. .. | C. ft. | 27·58 |
| 10 | Roofing with 1st class Mangalore tiles over 2″ x 1″ teak reepers wood oiling nails, etc., complete .. .. .. .. | 100 S. ft. | 8·16 |
| 11 | Ridge tiles set in mortar .. .. .. .. | R. ft. | 34 |
| 12 | Flooring with 6″ concrete and plastering with cement ½″ thick .. .. | 100 S. ft. | 3·78 |
| 13 | Chocolate painting, two coats .. .. .. .. | ,, | 156 |
| 14 | Chunam borders .. .. .. .. | R. ft. | 42 |
| 15 | Levelling ground, etc. .. .. .. .. | L. S. | |
| | (4) Constructing gram boiling shed— | | |
| 1 | Earthwork excavating foundation and filling in foundation and basement .. | 100 C. ft. | 540 |
| 2 | Burnt brick in mortar .. .. .. .. | ,, | 763 |
| 3 | Do mud .. .. .. .. | ,, | 1,179 |
| 4 | Archwork burnt brick in mortar .. .. .. | ,, | 32 |
| 5 | Burnt stone slabs 6″ thick one line dressed .. .. .. | S. ft. | 125 |
| 6 | Plastering with chunam .. .. .. .. | 100 S. ft. | 2,234 |
| 7 | White and colourwashing .. .. .. .. | ,, | 2,234 |
| 8 | Teakwood door battened with fittings as per Margat's specification, complete .. | S. ft. | 49 |
| 9 | Teakwood windows battened with ¾″ iron bars and fittings complete only one shutter outside as per Margat's specification. | ,, | 84 |
| 10 | Teakwood circular ventilators .. .. .. | ,, | 10 |
| 11 | Flooring with 1½″ Cuddappa slabs over 3″ concrete bed and cement pointing .. | 100 S. ft. | 224 |
| 12 | Teakwood work wrought and put up with wood oiling .. .. | C. ft. | 28·22 |
| 13 | Roofing with 1st class Mangalore tiles over 2″ x 1″ reepers with nails wood oiling, etc., complete. | 100 S. ft. | 616 |
| 14 | Ridge tiles set in mortar .. .. .. .. | R. ft. | 22 |
| 15 | Chunam borders .. .. .. .. | ,, | 44 |
| 16 | Levelling ground, etc. .. .. .. .. | L. S. | |
| | (5) Constructing a shoeing shed— | | |
| 1 | Earthwork excavating foundation and filling in foundation and basement .. | 100 C. ft. | 405 |
| 2 | Burnt brick in mortar .. .. .. .. | ,, | 398 |
| 3 | Burnt brick in mud .. .. .. .. | ,, | 889 |
| 4 | Burnt stone slabs 6″ thick one line dressed .. .. .. | S. ft. | 79 |
| 5 | Cutting grooves in the pillars .. .. .. .. | Each | 4 |
| 6 | Plastering with chunam .. .. .. .. | 100 S. ft. | 1,585 |
| 7 | Teakwood work wrought and put up with wood oiling .. .. | C. ft. | 67·26 |
| 8 | Roofing with 1st class Mangalore tiles over 2″ x 1″ teak reepers, nails, wood oiling, etc., complete. | 100 S. ft. | 1,350 |
| 9 | Ridge tiles set in mortar .. .. .. .. | R. ft. | 52 |
| 10 | Chunam borders .. .. .. .. | ,, | 40 |
| 11 | Preparing horse box and hearth, complete .. .. .. | L. S. | |
| 12 | Levelling ground, etc. .. .. .. .. | L. S. | |
| | (6) Constructing a Coffee shed— | | |
| 1 | Earthwork excavating foundation and filling in foundation and basement .. | 100 C. ft. | 1,053 |
| 2 | Burnt brick in mortar .. .. .. .. | ,, | 1,595 |
| 3 | Burnt brick in mud .. .. .. .. | ,, | 1,635 |
| 4 | Burnt stone slabs 6″ thick one line dressed .. .. .. | S. ft. | 295 |
| 5 | Plastering with chunam .. .. .. .. | 100 S. ft. | 3,611 |
| 6 | White and colourwashing .. .. .. .. | ,, | 3,611 |
| 7 | Teakwood pannelled doors with fittings complete as per Margat's specification .. | S. ft. | 196 |

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| 8 | Teakwood panelled windows with round iron bars, ½" thick with fittings complete, one shutter outside as per Margat's specifications. | S. ft. | 162 |
| 9 | Flooring with Cudappa slabs, 1½" thick over 3" concrete bed and cement painting. | 100 S. ft. | 630 |
| 10 | Teakwood work, wrought and put up, with wood oiling .. .. | C. ft. | 74 |
| 11 | Roofing with 1st class Mangalore tiles over 2" x 1" teak reepers, nails, wood oiling, etc., complete | 100 S. ft. | 1,339 |
| 12 | Ridge tiles set in mortar and 1" thick .. .. .. | R. ft. | 106 |
| 13 | Teakwood eave board, 9" deep with painting .. .. .. | " | 140 |
| 14 | Do finials do .. .. .. | Each | 4 |
| 15 | Chocolate painting .. .. .. .. | 100 S. ft | 716 |
| 16 | Zinc sheets for valleys .. .. .. .. | S. ft. | 32 |
| 17 | Teakwood planks, ½" thick for valleys .. .. .. | " | 32 |
| 18 | Levelling ground, etc. .. .. .. | Lump sum Rs. | |
| | (7) Constructing a shop— | | |
| 1 | Earthwork excavating foundation and filling in foundation and basement .. | 100 C. ft, | 841 |
| 2 | Burnt brick in mortar .. .. .. .. | " | 1,144 |
| 3 | Do mud .. .. .. .. | " | 1,222 |
| 4 | Burnt stone slabs, 6" thick, one side dressed .. .. .. | S. ft. | 167 |
| 5 | Plastering with chunam .. .. .. .. | 100 S. ft. | 2,795 |
| 6 | White and colourwashing .. .. .. .. | " | 2,795 |
| 7 | Teakwood panelled door, complete with fittings as per Margat's specifications .. | S. ft. | 74 |
| 8 | Do big doors with 1½" planks for shops with fittings .. | " | 56 |
| 9 | Do window panelled with ½" round iron bars, one shutter outside as per Margat's specifications. | " | 48 |
| 10 | Teakwood work, wrought and put up, with wood oiling .. .. | C. ft. | 53 |
| 11 | Roofing 1st class Mangalore tiles over 2" x 1" teak reepers, nails, wood oiling, etc., complete. | 100 S. ft. | 695 |
| 12 | Ridge tiles set in mortar .. .. .. | R. ft. | 29 |
| 13 | Roofing with pucca terraced, complete .. .. | 100 S. ft. | 185 |
| 14 | Brick masonry parapet wall including plastering and top cornice .. | R. ft. | 29 |
| 15 | Cornice, 9" complete .. .. .. .. | " | 40 |
| 16 | Chunam borders .. .. .. .. | " | 32 |
| 17 | Teakwood eave board, 9" deep and 1" thick, with painting .. .. | " | 25 |
| 18 | Chocolate painting, 2 coats .. .. .. .. | 100 S. ft. | 332 |
| 19 | Levelling ground and clearing site .. .. .. | Lump sum Rs. | |
| | (8) Adding front verandah for Quarter Guards and Prisons— | | |
| 1 | Dismantling and removing existing parapet wall .. .. | 100 C. ft. | 83 |
| 2 | Preparing stone brackets and inserting into the wall .. .. | Each | 4 |
| 3 | Teakwood work, wrought and put up, with wood oiling .. .. | C. ft | 50 |
| 4 | Roofing with 1st class Mangalore tiles over 2" x 1" teak reepers nails, wood oiling, complete. | 100 S. ft. | 300 |
| 5 | Ridge tiles set in mortar .. .. .. .. | R. ft. | 14 |
| 6 | Teakwood, 1" plank .. .. .. .. | S. ft. | 72 |
| 7 | Zinc sheet, 2' wide .. .. .. .. | " | 72 |
| 8 | Teakwood eave boards, 9" deep and 1" thick, with painting .. .. | R. ft. | 60 |
| 9 | Teakwood barge boards with finials and painting, complete .. .. | Each | 2 |
| 10 | Teakwood railings with painting .. .. .. | R. ft. | 40 |
| 11 | Removing and refixing doors and windows, masonry and plastering between the pillars of verandah. | Each | 3 |
| 12 | Chocolate painting .. .. .. | Lump sum Rs. | |

K. V. KARVE,
*Asst. Engineer,*

## CHITALDRUG DIVISION.

*Abstract Notification.*

The attention of the public is invited to the detail Notification published in pages 419 and 420 of the *Mysore Gazette* issue dated 21st July 1921, calling for tenders for Restoring the Hulemalali Minor Tank, Reg. No 143 of Holalkere Taluk.

Last date to receive tenders is 15th August 1921 and the earnest money to be deposited with tender is Rs. 100.

S. A RAMASWAMI IYER,
*Executive Engineer.*

## MYSORE IRON WORKS, BHADRAVATI.

*Dated 12th July* 1921

Notice is hereby given that tenders will be received at the Office of the Executive Engineer, Mysore Iron Works, Bhadravati, up to 31st July 1921, for the supply of Iron Fittings and Glass panes to the Bungalows in the New Town at Bhadravati. An approximate list or quantities is enclosed. These quantities are not guaranteed. The supply should be completed by the end of September 1921.